

PROJECT: H.013898 HEAVY LOAD MULTIMODAL 100,000 S.F. WAREHOUSE

ADDENDUM NO.: Two (2)

DATE: July 2, 2019

The following items shall be considered part of the Contract Documents and shall be included in same when Construction Contract is executed. Changes made by Addenda shall take precedence over original Documents.

This addendum consists of a total of **two (2)** pages.

1.0 QUESTIONS AND CLARIFICATIONS

1.1 THE BID OPEN DATE AND TIME IS HEREIN CHANGED TO THURSDAY, JULY 18, 2019 AT 4:00 PM.

1.2 The insulation drawn into the plans on the wall details and labeled #15 – R13 Min. Wall Insulation. The spec has this as a simple saver liner system. Should I quote a liner system or will the insulation be laminated compressed r13 between the girt and the wall sheeting?

Yes, please use a fabric liner system as specified in Spec Section 07230-3. Attached are sample photos of Liners.



- 1.3 All Requests For Information must be submitted no later than Friday, July 12, 2019 at 4:00 PM.
- 1.4 Revision to Addendum No. 1 – Item 1.3 – PVC may be used for under slab conduits. All stub-ups must be Rigid Metal Conduit (RMC).
- 1.5 WAYNE DALTON will not be considered as an equal substitution for OVERHEAD DOOR.
- 1.6 Maritime and Railroad insurance is not required.
- 1.7 A permit from the railroad is not required.
- 1.8 Awnings are to be supplied per the specifications indicated on the drawings.
- 1.9 Bridge cranes are to be provided and installed by the Contractor. Alternate manufacturers will be considered and approved if determined to be an equal substitution.
- 1.10 High capacity helical piers are not an approved substitution for the augur cast piles.
- 1.11 SIKAPLAN PVC based roofing is not approved for this project.
- 1.12 Excess spoil material may be deposited near the project site at a location specified by the Owner. Spoil material shall be free of any and all metals.

END OF ADDENDUM NO. 2