

**PORT RCC PHYSICAL SECURITY PROJECT
ENG. 19.013**

ADDENDUM NO. 1

**WEDNESDAY, JUNE 26, 2019
Pages total - 1**

GENERAL

1. Drawing Sheet A2 – Controls Note: Modify the note to read that **TWO** Click2enter Control Devices will be required. Contractor no longer has the option to provide just one. Exact location of both devices will be identified in the field.
2. Drawing Sheet A3 – Ground Floor Plan - Where the new concrete walk is being added, some existing landscaping will need to be removed. Contractor to have a landscape company carefully remove the existing bushes for relocation immediately adjacent to where the sidewalk is being installed. Field locate as required. Prep ground for relocation as needed then water. Keep watering for a period of 6 weeks at least three times a week unless mother nature waters it for you.
3. Drawing Sheet A3 – Detail D – Clarification: Pay attention to the note that requires the cutting of existing concrete curb to allow for overhead grill guides & grill to fully close to the surface of the concrete drive for maximum security. Curb to be cut neatly. Repair at and around the curb will be required as needed.

ATTACHMENTS

1. none